

Pre bid query replies:

S.No.	Bibber's Query	BRPL Reply
1	Whether the 1600 kVA CSS shall be Type 4 or Type 5.	Type 4.
2	Whether the transformer shall be filled with Synthetic Ester Oil or Mineral Oil.	Mineral Oil (ONAN).
3	Whether the required oil/winding temperature rise over an ambient temperature of 40°C shall be 55/60°C or 40/45°C.	40/45°C.
4	We understand that type testing on the complete CSS is not required. Kindly confirm.	All major components (RMU, Transformer, LT Panel, etc.) shall be type tested as per the applicable IS/IEC standards. Type testing of the complete assembly, including interconnections between major components, shall be as applicable. The requirement for type testing of the complete interconnected assembly shall be finalized during the technical evaluation
5	Please confirm whether a type-tested LV panel from Ultima (LK) is required.	Yes.
6	MCCB Utilization Category A shall be acceptable.	MCCB Utilization Category A shall be acceptable.
7	Phoenix make FRTU shall be acceptable.	Phoenix make FRTU is acceptable.